

KEY

- Existing Fairways, Greens & Tees
- Existing Bunkers
- Existing Ponds
- Existing Open Stream / Drainage Ditch as per Topographic Survey
- Proposed 500mm Contours

Drainage

- Existing Outfall Route - Stream / Ditch / Culvert, with Flow Direction Shown
- Existing Outfall Routes to be Culverted under Proposed Earthworks
- Proposed Earthworks Areas
- Proposed SW Drainage (Ditches / Land Drains Subject to Engineers Design)
- Existing Ditches Culverted where Affected by Proposed Earthworks
- Existing Ditches to be Removed
- Existing Manhole

0m 100m



Notes:

This is a **strategic** drainage plan for planning purposes only

Proposed new drainage shown (associated with proposed earthworks/mounds) is indicative only and subject to a drainage Engineers Detailed Design.

Any existing ditches that are affected by the locations of the proposed new mounds are to be culverted where required under the new raised ground levels, to maintain continuity of existing drainage system

