



PLEASE REFER TO GENERAL ARRANGEMENT DRAWING FOR PHASING

- PROPOSED TREES
- PROPOSED SPECIMEN SHRUB
- PROPOSED SHRUBS
- PROPOSED HEDGE
- PROPOSED COBBLE GARDEN (boulders, cobbles and 10% plants)
- PROPOSED GRASS (turf to gardens and seeding to POS)
- PROPOSED WILDFLOWER GRASS
- PROPOSED BENCH
- PROPOSED TREE PIT
- PROPOSED PLANTER

Rev G 06.12.25 Substation relocated
Rev F 17.11.25 Plant schedule fully quantified
Rev E 15.10.25 minor revisions - client comments
Rev D 13.08.25 minor revisions - client comments
Rev C 21.07.25 minor revisions - client comments
Rev B 28.04.25 minor revisions - client comments
Rev A 24.04.25 minor revisions - client comments



Chartered Landscape Architects
Story Homes
Edgehill Phases 6 & 7
Landscape Plan

DRAWING NUMBER: WWL-01G sheet 2 of 2

DATE: 21.04.25

SCALE: As shown @ A1

LANDSCAPE SPECIFICATION

TOPSOIL CULTIVATION In accordance with BS 3882. Apply glyphosate herbicide prior cultivation and allow the recommended period before further action. Ensure ground is free draining by breaking up subsoil and installation of land drainage as required. Do not work the soil in frozen or waterlogged condition. Remove any debris and stones greater than 50mm from surface and cultivate to suitable till for planting. Rake surface to achieve required level flush with adjacent paving for turf and 50mm below for planting to allow for mulch layer and smooth flowing contours for open space areas without hollows or soft areas. Topsoil depths to be minimum 150mm for grass and 450mm for planting and at least 300mm of suitable subsoil beneath the topsoil layer. Site topsoil to be supplemented with imported topsoil in accordance with BS 3882. Shrub beds in grass areas to be neatly cut to layout shown.

PLANTING Plant material shall conform to the National Plant Specification and be healthy, vigorous specimens, well rooted but not pot bound, free from pests and disease, hardy and undamaged by transport operations in accordance with HTA 'handling and establishing landscape plants'. Planting and turfing to be in accordance with BS 3936 and 4428. Plant species substitutes will be permitted to accommodate availability aid to include stock of particular good quality in nursery provided these are of a similar habit, size, colour, value etc and that they are approved in advance by the Landscape Architect. Native species to be local provenance. Bare root and rootballed plants to be planted between November and March. Bare root of planting holes and tree pits to be excavated to 300mm above G.L. with 50 x 100mm crossbar screwed to stakes. Rubber tree cushion nailed to crossbar and rubber tree belting nailed to secure tree. Single 75mm diameter stake for bare-rooted trees with rubber tree belting with spacer. Apply slow release fertiliser (16:10:10) at rate of 10g/sq.m. to planting areas and 250g per tree. Thoroughly water planting.

PLANTING DENSITIES/SETTING OUT Refer to the Planting Schedule for densities. Where a bed is indicated as mixed species on the plan the area should be divided equally between the species shown and the relevant density for that species applied to that proportion of the bed. Taller species to the rear of the bed and smaller species to the front planted in bold groups of single species and not mixtures unless clearly requested on the plan annotations.

TREE RABBIT GUARDS If rabbit activity is noted in the area and guarding is authorised each bare-rooted native plant hedge plant to receive a 12/14 weight 900mm cane and 60cm clear spiral guard. Trees to receive 90cm spiral guard. If extensive rabbit activity is observed rabbit fencing to ornamental areas will be required as directed by the Landscape Architect.

MULCH Spread 50mm layer of general purpose bark mulch, free from large sticks, and debris over all shrub areas, 800mm wide strips for hedging and 800mm diameter circles for tree pits in grass with neatly trimmed edge.

TURFING Following cultivation preparation specified above supply and lay Rolawn Halstone turf or similar approved with staggered joints close butted to uniform levels to finish 25mm above adjacent paving levels once well tamped down. Use sharp sand spread on surface to achieve fine tuning of levels. Thoroughly soak turf on completion and ensure regular watering is arranged until the turf has rooted. Do not turf in waterlogged or frozen conditions.

SEEDING AMENITY GRASS Following cultivation preparation specified above apply Bost on Seeds Low maintenance amenity mix or similar approved at a rate of 35g/sq.m. and roll with quad or hand drawn ballast grass roller. Apply water with sprinkler hose in dry conditions to ensure germination. Levels to be flush with adjacent paving following firming and settlement of topsoil. Further stone-picking, top-dressing and re-seeding of bare patches to ensure uniform, level grass is established. Re-roll as required at first cut stage.

SEEDING WILDFLOWER GRASS Prepare as for amenity grass and sow 3-5 g/sq.m. of mix E510M to general meadow areas and B57M to hedge margins supplied by Boston Seeds and applied in accordance with their recommendations.