



Feature bed at the end of the cul-de-sac as a focal point

Tall evergreen shrubs to screen the existing sub-station

Simple tree avenue within the grass verge with Spring bulb planting. Existing/stone wall kept open as a landscape feature

Climbing shrubs to garden boundary creates natural image to cul-de-sac

Flowering shrubs extend from the retained stone wall to an entrance feature bed

Evergreen flowering hedge to unify the image of the access road and enclose the front gardens. Managed at a low height.

Narrow canopy flowering Cherry trees enhance the streetscape without reducing light to windows

Existing trees and hedges

Proposed hedge

Proposed tree

Specimen shrub

Proposed grass

Proposed shrubs

Wild flower grass

POS (Landscape Management Area)

SCALE

0 10 20 30m

Focal point bed at high profile corner with flowering Cherry tree and bold shrub groups with specimens

Tall evergreen shrub planting to existing rear garden boundary to create a tidier unified image

Larger canopy trees add to the avenue where space permits with Spring bulbs in the grass verge

Tall flowering shrubs against the south-facing wall to create natural boundaries

Feature bed at junction creates some degree of enclosure to Plot 21 frontage

Sheltered beds with sunny aspect to have low flowering shrubs

Existing trees and sections of hedges to the boundary retained as far as possible and protected during the works

TOPSOIL CULTIVATION In accordance with BS 3882. Apply glyphosate herbicide prior cultivation and allow the recommended period before further action. Ensure ground is free draining by breaking up subsoil and installation of land drainage as required. Do not work the soil in frozen or waterlogged condition. Remove any debris and stones greater than 50mm from surface and cultivate to suitable tilth for planting. Rake surface to achieve required level flush with adjacent paving for turf and 50mm below for planting to allow for mulch layer and smooth flowing contours for open space areas without hollows or soft areas. Topsoil depths to be minimum 150mm for grass and 450mm for planting and at least 300mm of suitable subsoil beneath the topsoil layer. Site topsoil to be supplemented with imported topsoil in accordance with BS 3882. Shrub beds in grass areas to be neatly cut to layout shown.

PLANTING Plant material shall conform to the National Plant Specification and be healthy, vigorous specimens, well rooted but not pot bound, free from pests and disease, hardy and undamaged by transport operations in accordance with HTA 'handling and establishing landscape plants'. Planting and turfing to be in accordance with BS 3936 and 4428. Plant species substitutes will be permitted to accommodate availability and to include stock of particular good quality in nursery provided these are of a similar habit, size, colour, value etc and that they are approved in advance by the Landscape Architect. Native species to be local provenance. Bare root and rootballed plants to be planted between November and March. Backfill of planting holes and tree pits to be excavated topsoil with 25% by volume tree and shrub planting compost. Shrub pits to be generally 300 x 300 x 300mm or 75mm wider and deeper than the root spread. Tree pits to be 900 x 900 x 600mm or 150mm wider than the root spread. Stakes to be two 75mm diameter pointed stakes driven until firm and trimmed to 900mm above G.L. with 50 x 100mm crossbar screwed to stakes. Rubber tree cushion nailed to crossbar and rubber tree belting nailed to secure tree. Single 75mm diameter stake for bare-rooted trees with rubber tree belting with spacer. Apply slow release fertiliser (16:10:10) at rate of 100g/sq.m. to planting areas and 250g per tree. Thoroughly water planting.

Feature tree as a focal point at the end of the access road with tall flowering shrubs at the boundary

PLANTING DENSITIES/ SETTING OUT Refer to the Planting Schedule for densities. Where a bed is indicated as mixed species on the plan, the area should be divided equally between the species shown and the relevant density for that species applied to that proportion of the bed. Taller species to the rear of the bed and smaller species to the front planted in bold groups of single species and not mixtures unless clearly requested on the plan annotations.

TREE RABBIT GUARDS If rabbit activity is noted in the area and guarding is authorised each bare-rooted native plant hedge plant to receive a 12/14 weight 900mm cane and 60cm clear spiral guard. Trees to receive 90cm spiral guard. If extensive rabbit activity is observed rabbit fencing to ornamental areas will be required as directed by the Landscape Architect.

MULCH Spread 50mm layer of general purpose bark mulch, free from large sticks, and debris over all shrub areas, 800mm wide strips for hedging and 800mm diameter circles for tree pits in grass with neatly trimmed edge.

TURFING Following cultivation preparation specified above supply and lay Rolawn Medallion turf or similar approved with staggered joints close butted to uniform levels to finish 25mm above adjacent paving levels once well tamped down. Use sharp sand spread on surface to achieve fine tuning of levels. Thoroughly soak turf on completion and ensure regular watering is arranged until the turf has rooted. Do not turf in waterlogged or frozen conditions.

SEEDING AMENITY GRASS Following cultivation preparation specified above apply Bost on Seeds Low maintenance amenity mix or similar approved at a rate of 35gms/sq.m. and roll with quad or hand drawn ballast grass roller. Apply water with sprinkler hose in dry conditions to ensure germination. Levels to be flush with adjacent paving following firming and settlement of topsoil. Further stone-picking, top-dressing and re-seeding of bare patches to ensure uniform, level grass is established. Re-roll as required at first cut stage.

SEEDING WILDFLOWER GRASS Prepare as for amenity grass and sow 3-5 g/sq.m. of mix BS1M supplied by Boston Seeds and applied in accordance with their recommendations.

PLANTING SCHEDULE			
Type	Key	Specification	No/SQ.M.
TREES			
Alnus incana	AI	RB 8-10cm	N/A
Betula pendula	BP	RB 8-10cm	N/A
Crataegus pruinifolia	CP	RB 8-10cm	N/A
Crataegus Pauls Scarlet	CPS	RB 8-10cm	N/A
Prunus 'Pink Perfection'	PP	RB 8-10cm	N/A
Sorbus aria 'Lutescens'	SAL	RB 8-10cm	N/A
Sorbus aucuparia	SA	BR Feathered, 2-2.5m	
SPECIMENS			
Amelanchier lamarckii	AME	C10	N/A
Cotoneaster Cornubia	COT	C10	N/A
Eucymus ovalis	EO	C10	N/A
Phormium Yellow Wave	PY	C10	N/A
Pinus mugo	PM	C10	N/A
SHRUBS & HERBACEOUS			
Bergenia cordifolia	Bc	C2, 20-30cm	5
Ceanothus 'Autumnal Blue'	Ca	C2, 30-40cm	3
Cistus Silver Pink	Cs	C2, 20-30cm	3
Cotoneaster lacteus	Cl	C2, 30-40cm	3
Eucymus fortunei 'Blondy'	Eb	C2, 20-30cm	3
Eucymus fortunei 'Emerald Gaiety'	Ee	C2, 20-30cm	4
Escallonia 'Red Elf'	Er	C3, 30-40cm	3
Elaeagnus ebbingii	Ei	C2, 20-30cm	2
Geranium Johnsons Blue	GJ	C2, 10-15cm	5
Hebe 'Autumn Glory'	Hg	C5, 20-30cm	4
Hebe 'Blue Gem'	Hb	C5, 20-30cm	4
Hebe Midsummer Beauty	Hm	C2, 20-30cm	4
Hypericum Hidcote	Hy	C2, 20-30cm	3
Loncera nitida 'Maigreen'	Ln	C2, 20-30cm	3
Oleaster haastii	Oh	C2, 20-30cm	3
Potentilla 'Lovely Pink'	Pp	C2, 20-30cm	3
Senecio sunshine	Ss	C2, 20-30cm	3
Spiraea japonica 'Goldflame'	Sj	C2, 20-30cm	3
Vinca minor Atropurpurea	Vm	C2, 20-30cm	4
CLIMBERS			
Pyramcatha Red Column	Py	C3, 30-40cm	as shown
ORNAMENTAL HEDGE			
Escallonia rubra Macrantha	ERH	C3, 30-40cm	4/m
NATIVE HEDGE			
Prunus spinosa	NBH	5lin. m. double row	% MIX
Crataegus monogyna	Cra mon	BR, 45-60cm	60
Ilex aquifolium	Ile aqu	C3, 45-60cm	10
Corylus avellana	Cor ave	BR, 45-60cm	5
Sambucus nigra	Sam ng	C2, 45-60cm	5
Rosa canina	Ros can	BR, 45-60cm	5
Loncera periclymenum	Lon per	C2, 60-90cm	2
BULBS			
Narcissus			As Shown

REV A: Changes based on a new layout

22.02.21

Westwood
landscape

CHARTERED LANDSCAPE ARCHITECTS
www.westwoodlandscape.co.uk

**Gleeson Homes Ivy Mill,
Whitehaven**

Landscape Management Plan

DRAWING NO: GHIM-WW02-A

DATE: 27.01.21

SCALE: 1:250 @ A1